



TEST REPORT

Report No.: D3397.01-301-44

Rendered to:

INTERNATIONAL WINDOW Fullerton, CA

PRODUCT TYPE: Polyvinyl Chloride (PVC) Side Hinged Door (Outswing) SERIES/MODEL: 5021

SPECIFICATION: AAMA/WDMA/CSA 101/I.S.2/A440-08, NAFS - North American Fenestration Standard/Specification for Windows, Doors, and Skylights

Title	Summary of Results
	Class R – PG20 Size Tested 968 x 2440 mm
Primary Designators	(38 x 96 in) – Type SHD
	Class R – PG30 Size Tested 968 x 2440 mm
	(38 x 96 in) – Type LW SHD
Design Pressure	±1440 Pa (±30.08 psf)
Air Infiltration	0.7 L/s/m ² (0.13 cfm/ft ²)
Water Penetration Resistance	Test Pressure: 150 Pa (3.13 psf)

Test Completion Date: 02/05/15

Reference must be made to Report No. D3397.01-301-44, dated 10/07/16 for complete test specimen description and detailed test results.





Test Report No.: D3397.01-301-44 Report Date: 03/09/16 Revision 2 Date: 10/07/16 Record Retention End Date: 02/05/19 Page 1 of 7

1.0 Report Issued To:	International Window 1551 East Orangethorpe Avenue Fullerton, California 92831
2.0 Test Laboratory:	Architectural Testing, Inc. 2524 East Jensen Avenue Fresno, California 93706 (559) 233-8705

3.0 Project Summary:

- **3.1 Product Type**: Polyvinyl Chloride (PVC) Side Hinged Door (Outswing)
- 3.2 Series/Model: 5021
- **3.3 Compliance Statement**: Results obtained are tested values and were secured by using the designated test method(s). The specimen tested successfully met the performance requirements for the following ratings:

Class R – PG20 Size Tested 968 x 2440 mm (38 x 96 in) – Type SHD

Class R - PG30 Size Tested 968 x 2440 mm (38 x 96 in) - Type LW SHD

- **3.4 Test Dates**: 12/03/13 02/05/15
- **3.5 Test Record Retention End Date**: All test records for this report will be retained until February 5, 2019.
- **3.6 Test Location**: Architectural Testing test facility in Fresno, California.
- **3.7 Test Specimen Source**: The test specimen was provided by the client. Representative samples of the test specimen(s) will be retained by Architectural Testing for a minimum of four years from the test completion date.
- **3.8 Drawing Reference**: The test specimen drawings have been reviewed by Architectural Testing and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Architectural Testing per the drawings located in Appendix C. Any deviations are documented herein or on the drawings.
- 3.9 List of Official Observers:

<u>Name</u>

Company

David Douglass	Architectural Testing, Inc.
Jay Ratliff	Architectural Testing, Inc.



4.0 Test Specification(s):

AAMA/WDMA/CSA 101/I.S.2/A440-08, NAFS - North American Fenestration Standard/Specification for Windows, Doors, and Skylights.

5.0 Test Specimen Description:

5.1 Product Sizes:

Overall Area:	Width		Hei	ght
$2.36 \text{ m}^2 (25.4 \text{ ft}^2)$	millimeters	inches	millimeters	inches
Overall size	968	38-1/8	2440	96-1/16
Leaf	900	35-7/16	2365	93-1/8

5.2 Frame Construction:

Frame Member	Material	Description
Head, sill and jambs	PVC	Extruded.

Joint Location	Joinery Type	Detail
All corners	Mitered	Fully welded.

5.3 Leaf Construction:

Leaf Member	Material	Description
Rails and stiles	PVC	

Joint Location	Joinery Type	Detail
Top rail corners	Butted	Sealed; fastened through stile reinforcement using aluminum corner blocks and one 3/8-16 x 2-1/2" bolt and nut with washers.
Bottom rail corners	Butted	Sealed; fastened through stile reinforcement using aluminum corner blocks and two3/8-16 x 2-1/2" bolts and nuts with washers.

5.4 Weatherstripping:

Description	Quantity	Location
Wrapped foam gasket	1 Row	Head; sill; jambs.



Test Report No.: D3397.01-301-44 Report Date: 03/09/16 Revision 2 Date: 10/07/16 Record Retention End Date: 02/05/19 Page 3 of 7

5.0 Test Specimen Description: (Continued)

5.5 Glazing: No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.

Туре	Spacer	Interior& Exterior Glass	Glazing Method
3/4" IG	U Shaped steel	1/8" Tempered	Tape glazed and sealed with silicone to interior stop; secured with a snap-fit PVC bead.

Location	Quantity	Daylight	Opening	Dito
Location	Quantity	millimeters	inches	Dite
Leaf	1	656 x 2072	25-13/16 x 81-9/16	1/2"

5.6 Drainage:

Method	Size	Quantity	Location
Rectangular slot	1-1/4" x 1/4"	4	Sill face and two inner legs; spaced 5-1/2" and 8-3/8" from each end.
Rectangular slot	1" x 1/4"	4	Sill track; spaced 5-1/2" and 8-1/2" from each corner.

5.7 Hardware:

Description	Quantity	Location
Butt hinges	4	Jamb and stile; spaced 8-7/8" and 33-
		5/8" from each end; fastened to panel
		with four #8 x 1-1/4" screws into panel
		and five $#8x 1/2"$ screws into frame.
Latch/lock & handle	1	Lock stile; secured with four
assembly		#8 x 1/2" screws.
Latab strike		Jamb; spaced 35-1/2" from sill;
Laten strike 1		fastened with two $#8 \ge 1/2$ " screws.
Deadbolt strike	1	Jamb; spaced 41" from sill fastened
	1	with two #8 x 1/2" screws.





Test Report No.: D3397.01-301-44 Report Date: 03/09/16 Revision 2 Date: 10/07/16 Record Retention End Date: 02/05/19 Page 4 of 7

5.0 Test Specimen Description: (Continued)

5.8 Reinforcement:

Drawing Number	Location	Material
H50443	Top Rail	Extruded Aluminum.
H50444	Bottom Rail	Extruded Aluminum.
H50445	Hinge Stile	Extruded Aluminum.
H50446	Lock Stile	Extruded Aluminum.
H50442	Frame	Extruded Aluminum.

6.0 Installation:

The specimen was installed into a test buck fabricated from Douglas fir nominal 2x8 lumber. The rough opening allowed for a shim space of 1/4" each side. The exterior perimeter of the specimen was sealed to the rough opening with silicone.

Location	Anchor Description	Spacing
Through jambs	#8 x 2-1/2" Phillips flat head screw	2" from sill; 21" on center.
Through head	#8 x 2-1/2" Phillips flat head screw	2" from corners; midspan.

7.0 Test Results: The temperature during testing was 22-23°C (71-73°F). The results are tabulated as follows:

Title of Test	Results	Allowed	Note
Operating Force			
per ASTM E 2068			
Force to Latch	37 N (8.3 lbf)	Report Only	
Force to enable deadbolt	102 N (23.0 lbf)	Report Only	
Latch Operation	41 N (9.25 lbf)	100 N (22.5 lbf) max.	
Air Leakage			
per ASTM E 283		<u>Maximum</u>	
Infiltration at 75 Pa (1.57 psf)	$0.7 \text{ L/s/m}^2 (0.13 \text{ cfm/ft}^2)$	$1.5 \text{ L/s/m}^2 (0.3 \text{ cfm/ft}^2)$	1
Water Penetration			
per ASTM E 547	N/A	N/A	2
Uniform Load Deflection			
per ASTM E 330	N/A	N/A	2
Uniform Load Structural			
per ASTM E 330	N/A	N/A	2





Test Report No.: D3397.01-301-44 Report Date: 03/09/16 Revision 2 Date: 10/07/16 Record Retention End Date: 02/05/19 Page 5 of 7

7.0 Test Results: (Continued)

Title of Test	Results	Allowed	Note
Forced Entry Resistance			
per AAMA 1304,	Pass	No entry	
Thermoplastic Corner Weld	Pass	Meets as stated	
Vertical Loading Resistance			
Per Aama 925			
<u>Pre-Load – 200 N (45 Lbf)</u>			
Vertical Deflection	0.3 mm (0.01")		
Vertical Permanent Set	<0.1 mm (<0.01")		
<u>Test Load – 675 N (152 lbf)</u>			
Vertical Deflection	0.5 mm (0.02")		
Vertical Permanent Set	<0.1 mm (<0.01")		
Diagonal Deformation	<0.1 mm (<0.01")		
Force to Latch	36 N (8.0 lbf)		
Force To Enable Deadbolt	100 N (22.5 lbf)	Report only	
Operation Cycle			
Performance			
per AAMA 920			
25,000 cycles	Pass	Meets as stated	3
	Optional Performance	•	
Water Penetration			
per ASTM E 547 at			
150 Pa (3.13 psf)	Pass	No leakage	
Uniform Load Deflection			
per ASTM E 330			
<u>Lock Stile</u>	Deflection		
+1440 Pa (+30.08 psf)	0.5 mm (0.02")		
-1440 Pa (-30.08 psf)	0.5 mm (0.02")		
+2160 Pa (+45.11 psf)	1.0 mm (0.04")		
-2160 Pa (-45.11 psf)	0.5 mm (0.02")		
<u>Head</u>			
+1440 Pa (+30.08 psf)	1.8 mm (0.07")		
-1440 Pa (-30.08 psf)	2.8 mm (0.11")		
+2160 Pa (+45.11 psf)	2.5 mm (0.10")		4, 5,
-2160 Pa (-45.11 psf)	4.1 mm (0.16")	Report Only	6, 7



Test Report No.: D3397.01-301-44 Report Date: 03/09/16 Revision 2 Date: 10/07/16 Record Retention End Date: 02/05/19 Page 6 of 7

7.0 Test Results: (Continued)

Title of Test	Results	Allowed	Note
Uniform Load Structural			
per ASTM E 330			
<u>Lock Stile</u>	<u>Permanent Set</u>	<u>Maximum</u>	
+2160 Pa (+45.11 psf)	<0.1 mm (<0.01")	5.3 mm (0.21")	
-2160 Pa (-45.11 psf)	0.3 mm (0.01")	5.3 mm (0.21")	
Head			
+2160 Pa (+45.11 psf)	0.8 mm (0.03")	3.6 mm (0.14")	
-2160 Pa (-45.11 psf)	0.5 mm (0.02")	3.6 mm (0.14")	6, 7

Note 1: The tested specimen meets (or exceeds) the performance levels specified in AAMA/WDMA/CSA 101/I.S.2/A440 for air leakage resistance.

Note 2: The client opted to start at a pressure higher than the minimum required for this product designation. Test results are reported under Optional Performance.

Note 3: At the conclusion of the test, there were no signs of damage to the door panel, frame, construction, fasteners, glazing, weatherstripping, or system assembly.

Note 4: The deflections reported are not limited by AAMA/WDMA/CSA 101/I.S.2/A440 for this product designation. The deflections are included in this report for special code compliance and information only.

Note 5: Additional deflections are reported at pressures higher than required for this product designation. Test results are included at the request of the client.

Note 6: Loads were held for 10 seconds.

Note 7: Tape and film were used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.





Test Report No.: D3397.01-301-44 Report Date: 03/09/16 Revision 2 Date: 10/07/16 Record Retention End Date: 02/05/19 Page 7 of 7

Architectural Testing will service this report for the entire test record retention period. Test records such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by Architectural Testing, Inc. for the entire test record retention period.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written approval of Architectural Testing, Inc.

For ARCHITECTURAL TESTING, Inc.

Digitally Signed by: David

David Douglass Project Manager

DD/TW:ms

Digitally Signed by: Tyler Westerling

Tyler Westerling, P.E.

Senior Project Engineer

Attachments (pages): This report is complete only when all attachments listed are included. Appendix-A: Alteration Addendum (1) Appendix-B: Location of Air Seal (1) Appendix-C: Drawings (17)

This report produced from controlled document template ATI 00438, revised 06/27/14.