



TEST REPORT

Report No.: F2626.01-301-44

Rendered to:

INTERNATIONAL WINDOW Fullerton, California

PRODUCT TYPE: Polyvinyl Chloride (PVC) O/X Awning Projected Window **SERIES/MODEL**: 5321

SPECIFICATION: AAMA/WDMA/CSA 101/I.S.2/A440-11, NAFS 2011 - North American Fenestration Standard/Specification for Windows, Doors, and Skylights

Title	Summary of Results
AAMA/WDMA/CSA 101/I.S.2/A440-11	Class LC – PG30 1219 x 2404 (48 x 95) – Type AP
Design Pressure	±1440 Pa (±30.08 psf)
Air Infiltration	$0.6 \text{L/s/m}^2 (0.12 \text{cfm/ft}^2)$
Water Penetration Resistance	Test Pressure: 220 Pa (4.59 psf)

Test Completion Date:

04/15/16

Reference must be made to Report No. F2626.01-301-44, dated 06/21/16 for complete test specimen description and detailed test results.





Report Date: 06/02/16

Revision 1 Date: 06/21/16 Record Retention End Date: 04/15/20

Page 1 of 8

1.0 Report Issued To: International Window

1551 East Orangethorpe Avenue Fullerton, California 92831

2.0 Test Laboratory: Intertek-ATI

2524 East Jensen Avenue Fresno, California 93706

559-233-8705

3.0 Project Summary:

3.1 Product Type: Polyvinyl Chloride (PVC) O/X Awning Projected Window

3.2 Series/Model: 5321

3.3 Compliance Statement: Results obtained are tested values and were secured by using the designated test method. The specimen tested successfully met the performance requirements for the following rating:

Class LC - PG30 1219 x 2404 (48 x 95) - Type AP

3.4 Test Dates: 11/10/15 - 04/15/16

- **3.5 Test Record Retention End Date**: All test records for this report will be retained until April 15, 2020.
- **3.6 Test Location**: Intertek-ATI test facility in Fresno, California.
- **3.7 Test Specimen Source**: The test specimen was provided by the client. Representative samples of the test specimen will be retained by Intertek-ATI for a minimum of four years from the test completion date.
- **3.8 Drawing Reference**: The test specimen drawings have been reviewed by Intertek-ATI and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek-ATI per the drawings located in Appendix B. Any deviations are documented herein or on the drawings.

3.9 List of Official Observers:

<u>Name</u>	<u>Company</u>
Gino Vitali	Intertek-ATI
Dennis Janzen	Intertek-ATI
David Douglass	Intertek-ATI





Report Date: 06/02/16

Revision 1 Date: 06/21/16 Record Retention End Date: 04/15/20

Page 2 of 8

4.0 Test Specification:

AAMA/WDMA/CSA 101/I.S.2/A440-11, NAFS 2011 - North American Fenestration Standard/Specification for Windows, Doors, and Skylights

5.0 Test Specimen Description:

5.1 Product Sizes:

Overall Area:	Width		Height	
2.93 m ² (31.5 ft ²)	millimeters	inches	millimeters	inches
Overall Frame	1219	48	2404	94-5/8
Active and Fixed Panels	1183	46-9/16	1163	45-13/16

5.2 Frame Construction:

Frame Member	Material	Description
Head, Sill, Jambs, Mullion	PVC	Extruded; white

Joint	Joinery Type	Detail
All Corners	Mitered	Fully welded.
Horizontal Mullion	Notched and coped	Attached to frame using three #10 x 2-1/2" Phillips flat head screws through the frame with heads sealed in place.





Report Date: 06/02/16 Revision 1 Date: 06/21/16

Record Retention End Date: 04/15/20

Page 3 of 8

5.0 Test Specimen Description: (Continued)

5.3 Vent and Panel Construction:

Member	Material	Description
Rails, Stiles	PVC	Extruded; white

Joint	Joinery Type	Detail
Rails and Stiles	Mitered	Fully welded
Active Panel	Mitered	Additional corner bracket attached to glazing track corners with two #6 x 3/4" Phillips flat head self-drilling screws into each reinforcement.

5.4 Weatherstripping:

Description	Quantity	Location
Hollow Bulb Gasket	2 Rows	Coextruded with jambs, head, sill.
Hollow Bulb Gasket	4 Rows	Coextruded with mullion.
Single Leaf Gasket	1 Row	Coextruded with stiles, rails.

5.5 Glazing: No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.

Glass Type	Spacer Type	Glazing Method
3/4" IG	Steel Intercept	Set against 3/8" wide x 1/16" thick glazing tape; sealed at butted corner; secured with snap-fit exterior PVC bead.

Location	Interior/	Daylight Opening		D:-
	Exterior Glass	millimeters	inches	Bite
Active Panel	3/32" annealed	1107 x 1087	43-9/16 x 42-13/16	3/8"
Fixed Panel	1/8" annealed	1107 x 1087	43-9/16 x 42-13/16	3/8"





Report Date: 06/02/16 Revision 1 Date: 06/21/16

Record Retention End Date: 04/15/20

Page 4 of 8

5.0 Test Specimen Description: (Continued)

5.6 Drainage:

Drainage Method	Size	Quantity	Location
Weatherstripping Notch	1" wide	2	The exterior bulb gasket at the sill was notched 1-5/8" from jambs.

5.7 Hardware:

Description	Quantity	Location
		Assembled through sill and reinforcement
		at midspan using two Phillips head screws;
Rotary Operator	1	operator clip attached to bottom rail with
		two #6 x 1/2" Phillips flat head self-drilling
		screws into reinforcement.
Locking Handle	2	Jambs; 9-1/4" from sill; assembled through
Locking Handle	2	backing plate with two Phillips head screws.
Keeper	2	Active stiles; attached opposite locks using two #8
Keepei	2	x 1" Phillips truss head screws into reinforcement.
	3	Fastened to hinge stile with four #6 x 1"
Hinges		Phillips flat head self-drilling screws into
Tilliges		reinforcement; to horizontal mullion and sill
		with three #6 x 1/2" Phillips flat head.
Fixed Panel		Jambs, at 6" – 8" from corners and midspan;
Anchor Spacer,	9	horizontal mullion, at 4" – 6" from
3" Long		ends and midspan.
#6 X 1/2" Phillips	Each spacer	Attached to frame and mullion with
Flat Head Screw	Each space	two screws through aluminum spacer.
#9 X 2" Phillips	Der engeer	Attached to frame and mullion with one screw
Truss Head Screw	Per spacer	through glazing track and aluminum spacer.





Report Date: 06/02/16 Revision 1 Date: 06/21/16

Record Retention End Date: 04/15/20

Page 5 of 8

5.0 Test Specimen Description: (Continued)

5.8 Reinforcement:

Drawing Number	Location	Material
50201	Horizontal Mullion	Extruded aluminum
50218	Active Stiles and Rails Exterior Hollow	Extruded aluminum
Allmetal Air Spacer	Active Stiles and Rails Exterior Hollow	Roll-formed aluminum

5.9 Screen Construction: No screen was utilized.

6.0 Installation:

The specimen was installed into a nominal 2x8 Douglas fir wood test buck. The rough opening allowed for a 3/8" shim space. A continuous nominal 1x2 wood furring strip was placed over the mounting fin on all sides. The exterior perimeter of the window was sealed with silicone between the mounting fin and test buck.

Location	Anchor Description	Anchor Spacing
Head, Sill,	#6 x 1-5/8" Phillips flat head screws through	4" from corners;
Jambs	furring strip and mounting fin into test buck.	16" on center.





Report Date: 06/02/16

Revision 1 Date: 06/21/16 Record Retention End Date: 04/15/20

Page 6 of 8

7.0 Test Results: The temperature during testing was 23°C (73°F). The results are tabulated as follows:

Title of Test	Results	Allowed	Note
Operating Force			
per ASTM E 2068			
Initiate motion	7 N (1.5 lbf)	Report Only	
Maintain motion	13 N (3 lbf)	30 N (6.7 lbf) max.	
Latches	56 N (12.5 lbf)	100 N (22 lbf) max.	
Air Leakage			
per ASTM E 283		<u>Maximum</u>	
75 Pa (1.57 psf) Infiltration	$0.6 \text{L/s/m}^2 (0.12 \text{cfm/ft}^2)$	$1.5 \text{ L/s/m}^2 (0.3 \text{ cfm/ft}^2)$	1
75 Pa (1.57 psf) Exfiltration	$0.6 \text{ L/s/m}^2 (0.12 \text{ cfm/ft}^2)$		
Water Penetration			
per ASTM E 547	N/A	N/A	2
Uniform Load Deflection			
per ASTM E 330			
<u>Horizontal Mullion</u>	Deflections		
+1200 Pa (+25.06 psf)	4.1 mm (0.16")		
-1200 Pa (-25.06 psf)	4.1 mm (0.16")		
Active Bottom Rail			
+1200 Pa (+25.06 psf)	1.1 mm (0.05")		
-1200 Pa (-25.06 psf)	17.1 mm (0.68")	Report Only	3, 4, 5
Uniform Load Structural			
per ASTM E 330			
<u>Horizontal Mullion</u>	<u>Permanent Sets</u>	<u>Maximum</u>	
+1800 Pa (+37.59 psf)	0.3 mm (0.01")	4.8 mm (0.19")	
-1800 Pa (-37.59 psf)	0.1 mm (0.01")	4.8 mm (0.19")	
Active Bottom Rail			
+1800 Pa (+37.59 psf)	0.1 mm (0.01")	4.7 mm (0.19")	
-1800 Pa (-37.59 psf)	0.4 mm (0.02")	4.7 mm (0.19")	4, 5
Thermoplastic Corner	Pass	Meets as stated	
Weld	1 433	Meets as stated	
Awning, Hopper,			
Projected Hardware Load			
70 N (15 lbf)	19.8 mm (0.78")	Report Only	
Forced Entry Resistance			
per ASTM F 588, Type B	Grade 10	No entry	





Report Date: 06/02/16

Revision 1 Date: 06/21/16 Record Retention End Date: 04/15/20

Page 7 of 8

7.0 Test Results: (Continued)

Title of Test	Results	Allowed	Note	
Optional Results				
Water Penetration				
per ASTM E 547				
220 Pa (4.59 psf) – Cyclic	Pass	No leakage		
Uniform Load Deflection				
per ASTM E 330				
<u>Horizontal Mullion</u>	Deflections			
+1440 Pa (+30.08 psf)	5.1 mm (0.20")			
-1440 Pa (-30.08 psf)	5.5 mm (0.22")			
Active Bottom Rail				
+1440 Pa (+30.08 psf)	1.5 mm (0.06")			
-1440 Pa (-30.08 psf)	21.0 mm (0.83")	Report Only	3, 4, 5	
Uniform Load Structural				
per ASTM E 330				
<u>Horizontal Mullion</u>	Permanent Sets	<u>Maximum</u>		
+2160 Pa (+45.11 psf)	0.3 mm (0.01")	4.8 mm (0.19")		
-2160 Pa (-45.11 psf)	0.1 mm (0.01")	4.8 mm (0.19")		
Active Bottom Rail				
+2160 Pa (+45.11 psf)	<0.1 mm (<0.01")	4.7 mm (0.19")		
-2160 Pa (-45.11 psf)	2.2 mm (0.09")	4.7 mm (0.19")	4, 5	
Awning, Hopper,				
Projected Hardware Load	<u>Deflection</u>			
140 N (30 lbf)	22.4 mm (0.88")	Report Only		

- **Note 1:** The tested specimen meets (or exceeds) the performance levels specified in AAMA/WDMA/CSA 101/I.S.2/A440 for air leakage resistance.
- **Note 2:** The client opted to start at a pressure higher than the minimum required. Test results are reported under Optional Performance
- **Note 3:** The deflections reported are not limited by AAMA/WDMA/CSA 101/I.S.2/A440 for this product designation. The results are reported for special code compliance and information only.
- Note 4: Loads were held for 10 seconds.
- **Note 5:** The use of tape and film to seal against air leakage during uniform load testing did not, in the opinion of the Intertek ATI witness, influence the test results.





Report Date: 06/02/16 Revision 1 Date: 06/21/16

Record Retention End Date: 04/15/20

Page 8 of 8

Intertek-ATI will service this report for the entire test record retention period. Test records such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by Intertek-ATI for the entire test record retention period.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written approval of Intertek-ATI

For Intertek-ATI

Digitally Signed by: David Douglass

David Douglass Project Manager leak Kine

Digitally Signed by:Leaton Kirk

Leaton Kirk
Director – Regional Operations

KCW/DD:ms

Attachments (pages): This report is complete only when all attachments listed are included.

Appendix-A: Alteration Addendum (1)

Appendix-B: Drawings (17)

This report produced from controlled document template ATI 00438, revised 06/27/14.





Report Date: 06/02/16 Revision 1 Date: 06/21/16 Record Retention End Date: 04/15/20

Revision Log

<u>Rev. #</u>	<u>Date</u>	Page(s)	Revision(s)
0	06/02/16	N/A	Original Report Issue.
1	06/21/16	2	Corrected Panel Dimensions.
		3	Corrected DLO Dimensions.





Report Date: 06/02/16 Revision 1 Date: 06/21/16

Record Retention End Date: 04/15/20

Appendix A

Alteration Addendum

Alteration #1: Date – 11/10/2015

Cause for alteration - water leakage

Remedial action taken – sealed fixed glazing corners and operator cover

Alteration #2: Date – 12/21/2015

Cause for alteration – water leakage

Remedial action taken - trimmed vinyl and gasket at sill corner welds

Alteration #3: Date – 3/11/2016

Cause for alteration - water leakage

Remedial action taken - added weeps to fixed bottom rail